

MAINTENANCE OF BITUMEN ROADS IN ORANJEMUND TOWN
Schedule 4

SECTION: BASE

ITEM NO	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT (N\$)
3	SABS 1200 C	ROADWORKS (GENERAL)				
		ROAD ON THE NORTHERN SIDE OF THE BUSINESS PARK - (181 m length)				
	PSC 1	Clear site, remove shrubs, remove excess material and any structures, levelling etc as directed by Engineer	Sum	1	PC Sum	4,000.00
	1200 DM	Rip Roadbed , mix and compaction of existing material minimum of to 90% MOD AASHTO maximum density	m ³	298.65		
	1200 ME	Import G7 material from designated borrow pit for SSG , mix and compact a layer of 150 mm to 93% MOD AASHTO minimum density.	m ³	162.90		
	1200 MF	Import G5 material from designated borrow pit for Subbase , mix and compact a layer of 150 mm to 95% MOD AASHTO minimum density.	m ³	162.90		
	1200 MJ	Construction of segmentated paving complete with 20mm sand (80 mm class 35, grey, interlocking paving)	m ²	1090.04		
	1200 MJ		m ²	686.06		
	1200 MK	Construction of a concrete edgebeam completely (300mm x 150mm)	m	22.9		
4		TRAFFIC CALMING STRUCTURES				
	4.1	DR. HAGE GEINGOB AVENUE				
	4.1.2	Supply, delivery and installation of speed humps as per attached drawing and their associated notes. (rate is to include material, labour and plant costs)	No	2.0		
	4.2	ROAD TO THE BEACH AREA				
	4.2.1	Erection of premix rumble strips (9 bars - 200mm strip and 200mm spacing with a total , 13.2mm aggregate) as indicated by the Engineer	No	4.0		
	4.2.2	Erection of Road studs / cat eyes (White / Red / Yellow)	kg	3.0		
Total Carried Forward To Summary						