

MAINTENANCE OF BITUMEN ROADS IN ORANJEMUND TOWN

Schedule 6

SECTION: KERBING AND CHANNELLING

ITEM	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT N\$
5	SABS 1200 MK	KERBING AND CHANNELLING				
5.1		PRECAST CONCRETE KERBING WITHOUT PRECAST EDGE CHANNELING				
5.1.1		Remove and reinstate existing mountable or barrier kerbs including concrete bedding	m			Rate only
5.1.2		Install new mountable or barrier kerbs including concrete bedding	m			Rate only
5.2		PRECAST CONCRETE KERBING WITH PRECAST EDGE CHANNELING				
5.2.1		Remove and reinstate existing mountable or barrier kerbs including concrete bedding	m			Rate only
5.2.2		Install new mountable or barrier kerbs including concrete bedding and channel	m			Rate only
5.3		New Concrete Edge Beam				
		Construct 250mm x 300mm deep, concrete road edge restraints, Class 25/19 including construction joints at 0.9m	m ³	1.05		
Total Carried Forward To Summary						